

Plan: 260701 Sitework Civil SW Combine T1 [1/27]

260701_ Site Work Civil SW REV T1 (PIPELINE)

Item	Total
 100MM PVC DWV SN8	144.59 m
 RCP 375mm CLASS 3	351.55 m
 RCP 375mm CLASS 4	30.40 m
 100mm PVC 90 Deg Bend	1 EA
 100mm PVC 45 Deg Bend	1 EA
 100mm PVC 45 Deg Junction	15 EA

260701_ Site Work Civil SW RE T1 (CULVERT)

Item	Total
 RCBC 1200X600	17.77 m
 RCBC 1500X600	29.04 m

260701_ Site Work Civil SW REV T1 Pit Structural cOUNT (Headwall , Pit etc .)

Item	Total
 HEADWALL TO SUIT 375 mm RCP	3 EA
 Headwall to suit RCBC 1200X600	2 EA
 Headwall to suit RCBC 1500X600	1 EA
 INLET (ON-GRADE, 2.4 m RGU)	10 EA
 INLET (SAG, 2.4 m RGU)	4 EA
 1050 CHAMBER (CHAMBER ,ASPRO 900X600 COVER)	1 EA
 PIPE TO PIPE CONNECTION (375MM RCP /RCBC 1500 X600)	1 EA

260701_ Site Work Civil SW REV T1 subsoil

Item	Total
 Subsoil drain	1013.49 m

260701_ Site Work Civil SW REV T 1 Grated Trench Drain

Item	Total
 GT1. RECYFIX PRO 200 CLASS B 125, TYPE 010 WITH FIBRETEC SLOTTED GRATING	23.61 m

260716_ Site Work Civil SW REV T1 ROCK AND EROSION CONTROL MATTING for kerb chute

Item	Total
 ROCK :DIA 100 , 180 thickness, allow for erosion control matting	45.50 m ²

260716_ Site Work civil SW REV T1 ROCK FOR HEADWALL OF CULVERT INLET/OUT LET

Item	Total
 D50=200mm Depth 360 mm	22.50 m ²
 d50=100, 180MM THICKNESS	73.03 m ²