

Plan: 260701 Sitework Civil SW Combine T1 [3/27]

260701_ Site Work Civil SW REV T1 (PIPELINE)

Item	Total
 100MM PVC DWV SN8	36.81 m
 150MM PVC DWV SN8	20.64 m
 RCP 375mm CLASS 3	45.45 m
 RPC 600 CLASS 3	3.31 m
 225mm HDPE PN100 SN8	15.76 m
 300MM HDPE PN100 SN8	9.03 m
 375mm HDPE PN100 SN8	197.05 m
 450mm HDPE PN100 SN8	41.47 m
 600mm HDPE PN100 SN8	38.47 m
 100mm PVC 45 Deg Junction	3 EA

260701_ Site Work Civil SW RE T1 (CULVERT)

Item	Total
 RCBO 750 X300	5.17 m

260701_ Site Work Civil SW REV T1 Pit Structural cOUNT (Headwall , Pit etc .)

Item	Total
 HEADWALL TO SUIT 375 mm RCP	1 EA
 Headwall to suit 300mm HDPE	1 EA
 Headwall to suit RCBC 750X300	1 EA
 Headwall to suit RCBC 1500X600	1 EA
 INLET (ON-GRADE, 2.4 m RGU)	4 EA
 1050 CHAMBER (CHAMBER ,ASPRO 900X600 COVER)	2 EA
 1200 Chamber (chamber ,aspro , 900x600 covr)	3 EA

260701_Site Work Civil SW REV T1 Pit Structural cOUNT (Headwall , Pit etc .)

Item	Total
 PIPE TO PIPE CONNECTION (375 HDPE , 150 PVC)	9 EA
 PIPE TO PIPE CONNECTION (375 RPC , 100 PVC)	1 EA
 PIPE TO PIPE CONNECTION (450 HDPE , 150 PVC)	2 EA
 PIPE TO PIPE CONNECTION (600 HDPE , 150 PVC)	1 EA
 WSUD TREATMENT,	1 EA
 HAURATON TRASH BOX 200	15 EA

260701_Site Work Civil SW REV T1 subsoil

Item	Total
 Subsoil drain	359.01 m

260701_Site Work Civil SW REV T 1 Grated Trench Drain

Item	Total
 GT1. RECYFIX PRO 200 CLASS B 125, TYPE 010 WITH FIBRETEC SLOTTED GRATING	105.12 m
 GT2 RECYFIX PRO 200 CLASS B 125, TYPE 010 WITH FIBRETEC SLOTTED GRATING	66.58 m
 GT3 RECYFIX PRO 200 CLASS B 125, TYPE 010 WITH FIBRETEC SLOTTED GRATING	68.16 m
 GT4 RECYFIX PRO 200 CLASS B 125, TYPE 010 WITH FIBRETEC SLOTTED GRATING	66.81 m

260716_Site Work civil SW REV T1 ROCK FOR HEADWALL OF CULVERT INLET/OUT LET

Item	Total
 D50=200mm Depth 360 mm	47.90 m ²
 d50=100, 180MM THICKNESS	10.00 m ²