

Plan: 260701 Sitework Civil SW Combine T1 [4/27]

260701_ Site Work Civil SW REV T1 (PIPELINE)

Item	Total
 100MM PVC DWV SN8	102.31 m
 150MM PVC DWV SN8	28.77 m
 225mm PVC DWV SN8	180.93 m
 RCP 375mm CLASS 3	71.61 m
 225mm HDPE PN100 SN8	20.48 m
 300MM HDPE PN100 SN8	49.53 m
 375mm HDPE PN100 SN8	4.68 m
 100mm PVC 90 Deg Bend	16 EA
 100mm PVC 45 Deg Bend	8 EA
 225 mm PVC 90 Deg Bend	1 EA
 100mm PVC 45 Deg Junction	8 EA
 225mm PVC 45 Deg Junction	1 EA
 225mm X100mm PVC 45 Deg Junction	11 EA
 INSPECTION OPENING WITH GALVANISED COVER FLUSH WITH SURFACE	3 EA

260701_ Site Work Civil SW RE T1 (CULVERT)

Item	Total
 RCBC 600X300	15.39 m

260701_ Site Work Civil SW REV T1 Pit Structural cOUNT (Headwall , Pit etc .)

Item	Total
 Headwall to suit 225 PVC Pipe	2 EA
 Headwall to suit RCBC 600X300	4 EA
 INLET (ON-GRADE, 2.4 m RGU)	3 EA

260701_Site Work Civil SW REV T1 Pit Structural cOUNT (Headwall , Pit etc .)

Item	Total
 INLET (SAG, 2.4 m RGU)	1 EA
 1050 CHAMBER (CHAMBER ,ASPRO 900X600 COVER)	6 EA
 PIPE TO PIPE CONNECTION (300 HDPE , 150 PVC)	1 EA
 HAURATON TRASH BOX 100	4 EA
 HAURATON TRASH BOX 200	2 EA
 600x600 pit ,grate (type 2)	1 EA

260701_Site Work Civil SW REV T1 subsoil

Item	Total
 Subsoil drain	295.30 m

260701_ Site Work Civil SW REV T 1 Grated Trench Drain

Item	Total
 GT2 RECYFIX PRO 200 CLASS B 125, TYPE 010 WITH FIBRETEC SLOTTED GRATING	77.20 m
 GT5 RECYFIX PRO 100 CLASS B 125, TYPE 010 WITH STAINLESS STEEL ANTI-SLIP HEELGUARD GRATING	15.21 m
 GT6 RECYFIX PRO 200 CLASS D 400, TYPE 010 WITH HEELGUARD G-TEC DUCTILE IRON GRATING	31.75 m
 GT7 RECYFIX PRO 100 CLASS B 125, TYPE 010 WITH STAINLESS STEEL ANTI-SLIP HEELGUARD GRATING	3.58 m
 GT8 RECYFIX PRO 100 CLASS B 125, TYPE 010 WITH STAINLESS STEEL ANTI-SLIP HEELGUARD GRATING	6.01 m
 GT9 RECYFIX PRO 100 CLASS B 125, TYPE 010 WITH STAINLESS STEEL ANTI-SLIP HEELGUARD GRATING	3.65 m

260716_Site Work civil SW REV T1 ROCK FOR HEADWALL OF CULVERT INLET/OUT LET

Item	Total
 d50=100, 180MM THICKNESS	26.36 m²