

Plan: 260701 Sitework Civil SW Combine T1 [5/27]

260701_ Site Work Civil SW REV T1 (PIPELINE)

Item	Total
 150MM PVC DWV SN8	9.92 m
 RCP 375mm CLASS 3	12.37 m
 225mm HDPE PN100 SN8	101.43 m
 375mm HDPE PN100 SN8	8.70 m

260701_ Site Work Civil SW RE T1 (CULVERT)

Item	Total
 RCBC 600X300	8.27 m

260701_ Site Work Civil SW REV T1 Pit Structural cOUNT (Headwall , Pit etc .)

Item	Total
 HEADWALL TO SUIT 2 X 375 mm RCP	2 EA
 Headwall to suit RCBC 600X300	2 EA
 1050 CHAMBER (CHAMBER ,ASPRO 900X600 COVER)	4 EA
 PIPE TO PIPE CONNECTION (225 HDPE , 150 PVC)	4 EA
 HAURATON TRASH BOX 200	8 EA

260701_ Site Work Civil SW REV T 1 Grated Trench Drain

Item	Total
 GT3 RECYFIX PRO 200 CLASS B 125, TYPE 010 WITH FIBRETEC SLOTTED GRATING	77.26 m
 GT4 RECYFIX PRO 200 CLASS B 125, TYPE 010 WITH FIBRETEC SLOTTED GRATING	77.15 m

260716_Site Work civil SW REV T1 ROCK FOR HEADWALL OF CULVERT INLET/OUT LET

Item	Total
 d50=100, 180MM THICKNESS	22.17 m ²