


INLET INVERT LEVEL
MINIMUM 100mm ABOVE
OUTLET INVERT LEVEL



The diagram shows a cross-section of a Stormfilter unit. It is a cylindrical device with a concrete base. The internal components are labeled as follows:

- AIR LOCK CAP WITH CHECK VALVE**: Located at the top of the unit.
- LIFTING TAB**: A small tab on the top of the unit.
- FILTER MEDIA**: The main filtering layer, shown as a dark, porous material.
- CENTRE TUBE**: A vertical tube running through the center of the filter media.
- SCRUBBING REGULATOR**: A component on the side of the unit, used to adjust the flow rate.
- OUTER MESH**: A mesh screen located below the filter media.
- UNDER-DRAIN MANIFOLD**: A horizontal pipe at the bottom of the unit for collecting filtered water.
- HOOD**: The top cover of the unit.
- CONCRETE FALSE FLOOR**: The base of the unit, which is a concrete slab.
- FLOW RESTRICTOR DISC**: A disc located at the bottom of the center tube.
- CHAMBER FLOOR**: The floor of the chamber, which is a concrete slab.

STORMFILTER DESIGN PARAMETERS

- STORMFILTER TREATMENT CAPACITY VARIES BY NUMBER OF FILTER CARTRIDGES INSTALLED.
- THE STANDARD CONFIGURATION IS SHOWN. ACTUAL CONFIGURATION OF THE SPECIFIED STRUCTURE(S) PER CERTIFYING ENGINEER WILL BE SHOWN ON SUBMITTAL DRAWING(S).
- FILTER CARTRIDGES SHALL BE MEDIA-FILLED, PASSIVE, SIPHON ACTUATED, RADIAL FLOW, AND SELF-CLEANING. RADIAL MEDIA DEPTH SHALL BE 178mm.

NUMBER OF CARTRIDGES	20
HYDRAULIC CAPACITY (L/S)	90
MAX. COMPONENT WEIGHT (kg)	13000
*MASS VARIABLE	
TANK LID WEIGHT (kg)	5100

CARTRIDGE NAME / SIPHON HEIGHT (mm)	690	460	310
CARTRIDGE PHYSICAL HEIGHT (mm)	840	600	600
TYPICAL WEIR HEIGHT [H] (mm)	920	690	540
MINIMUM INTERNAL HEIGHT [A] (mm)	1100	850	850
CARTRIDGE FLOW RATE FOR NPSORB MEDIA (L/s)	1.60	1.10	0.70
CARTRIDGE FLOW RATE FOR PSORB (MCC) MEDIA (L/s)	0.90	0.46	0.39
CARTRIDGE FLOW RATE FOR PSORB (SQIDEF) MEDIA (L/s)	1.26	0.86	0.60
CARTRIDGE FLOW RATE FOR ZPG MEDIA (L/s)	1.60	1.10	0.70

INSTALLATION NOTES

1. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY CERTIFYING ENGINEER.
2. CONTRACTOR TO PROVIDE ALL EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STORMFILTER STRUCTURE (LIFTING DETAIL PROVIDED SEPARATELY).
3. CONTRACTOR TO APPLY SEALANT TO ALL JOINTS AND TO PROVIDE, INSTALL, AND GROUT INLET AND OUTLET PIPES.



www.oceanprotect.com.au

OCEAN PROTECT 20 CARTRIDGE STORMFILTER SYSTEM DN3300 MANHOLE SPECIFICATION DRAWING