

PART 2 – TECHNICAL SPECIFICATIONS

1. INTRODUCTION

Rockhampton Regional Council invites suitably qualified and experienced contractors to submit a tender for the delivery of Stage 1 of the Rockhampton Sports Precinct, a landmark multi-staged recreation and sporting development intended to serve the region's growing sporting community and strengthen its capacity to host training, competition, and sporting events.

Stage 1 comprises the establishment of the new Home of Netball, featuring the construction of 16 asphalt acrylic-surface netball courts, each designed and lit to competition standards to support training, community sport, and high-level competitive fixtures. The project also includes a modern clubhouse, public amenities, and a master planned playground, ensuring the precinct provides not only a high-performance sporting environment but also a welcoming, family-friendly community space.

To support functionality and safe public access, Stage 1 incorporates the development of new carparks, a new entry road, and all associated site services required for ongoing operational reliability. These works will be complemented by comprehensive landscaping, creating an accessible and attractive environment that aligns with the broader vision for the Rockhampton Sports Precinct.

As the first phase of a larger multi-stage program, this package sets the foundation for future development, establishing key infrastructure that will unlock subsequent stages and contribute to a cohesive, high-quality sporting precinct for the Rockhampton community.

2. DEFINITIONS

Tenderers shall refer to the following definitions used throughout the specification:

ADAC	Asset Design As Constructed
AS	Australian Standard
BIM	Building Information Model
CAD	Computer Aided Drafting
CQU	Central Queensland University
ISO	International Organization for Standardization
ITP	Inspection and Test Plan
NATA	National Association of Testing Authorities
PCBU	Person Conducting a Business or Undertaking
RPEQ	Registered Professional Engineer of Queensland
RSP	Rockhampton Sports Precinct
Stage 1	Home for Netball
The Contractor	The successful tenderer engaged to perform the works (The Principal Contractor)
The Principal	Rockhampton Regional Council (RRC)

3. SITE DETAILS

Site Address: 554-700 Yaamba Road, Norman Gardens, QLD 4701

Site Description: The site is predominantly characterised by regrowth and undeveloped land within the broader Rockhampton Sports Precinct masterplan area.

Site Area: approximately 91,270m²

Current Use: CQU Vacant/open land reserved for Education purposes



Figure 1 RSP Stage 1 Net Ball Location

4. DETAILED REQUIREMENTS

The Contractor shall supply all labour, materials, equipment, plant, delivery, crantage, supervision, testing, commissioning, certification, and all associated works necessary to deliver the complete Stage 1 (Netball) Scope of Works as defined in this specification and the accompanying drawings and discipline specifications. All work must be completed in strict accordance with all contract documentation, including but not limited to the drawings, specifications, schedules, technical requirements, and any issued revisions or addenda.

All activities shall be carried out in a safe, competent, and professional manner and must comply with all relevant legislation, Australian Standards, codes of practice, industry guidelines, and project-specific requirements. The Contractor is responsible for ensuring that all workmanship, materials, installation methods, and delivered outcomes fully meet the requirements of the contract and achieve the intended design, performance, and quality standards for the Rockhampton Sports Precinct – Stage 1 works.

The Scope of Work shall comprise of the construction of all elements as described below, but is not limited to the items listed, and shall be undertaken strictly in accordance with the entire Contract Documentation, including all drawings, specifications, schedules, reports, and any instructions issued by the Principal or Principal's Representative.

4.1. NETBALL COURTS

- Construct 16 competition-standard asphalt netball courts, runoff and pedestrian space.
- Apply CoolTop sports surface system (or approved equal) including all coatings, line marking and numbering.
- Install competition-level sports lighting, including pit & duct, poles, luminaires, cabling and controls.
- Installation of netball posts, nets & pads
- Provide court perimeter edging, drainage and associated civil works.

4.2. NETBALL CLUBHOUSE

- Construct a new netball clubhouse facility, including all piles, footings, slab, structural framing, roofing, cladding, linings, ceilings, and architectural finishes.
- Provide full internal fit-out including amenities, changerooms, storage areas, kiosk/canteen (if specified), meeting rooms, office/administration spaces, and any additional functional spaces identified in the Contract Documentation.
- Install all building services including electrical, lighting, mechanical (HVAC), hydraulics (water, sewer, stormwater), communications, security, fire safety systems, and any specialist systems required to meet operational needs.
- Provide all external works associated with the building, including accessible ramps, paths of travel, hardstand areas, building perimeter drainage, connections to utilities, and service entries.
- Ensure the building is completed to meet all relevant accessibility requirements, building codes, sporting facility standards, and compliance obligations.
- Provide all fixtures, fittings, equipment, and operational components necessary for a complete and functional clubhouse as described in the Contract Documentation.

4.3. ACCESS ROAD & STREET LIGHTING

- Construct a new entry access road including pavement, kerb and channel.
- Install all line marking, traffic signage, and compliant street lighting and entry signage.
- Provide tie-ins to new intersection works, roundabout and carpark accesses.

4.4. CAR PARKING

- Construct new car parking areas, including pavements, kerbing, line marking, wheel stops and traffic signage and bollards.
- Install carpark lighting and electrical reticulation.

4.5. PUBLIC AMENITIES BUILDING

- Construct a new public amenities building, including all piles, footings, slab, structural framing, roofing, cladding, linings, ceilings, and architectural finishes and mechanical (HVAC) services.
- Connect to all required services (water, sewer, power, comms).

4.6. PLAYGROUNDS, SPORTS COURTS & EMBELLISHMENTS

- Construct new playground areas and sport courts including equipment, Softfall, edging, shade/protection elements (if specified) and associated furniture.
- Provide all ancillary embellishments such as shelters, seating, tables, BBQ's, bins, paths, fencing and bike racks

4.7. LANDSCAPING & IRRIGATION

- Install irrigated landscaping across the site, including turf, planting, soil preparation and mulching.
- Provide automatic irrigation system with connection to water supply as per provided specifications.

4.8. CIVIL & SERVICES INFRASTRUCTURE

- Construct full stormwater drainage system, including pits, pipes, subsoil, overland flow paths and water-quality filter system.
- Provide sewerage infrastructure, including a sewer pump station and rising main to utility connection.
- Install water, power, and electrical reticulation throughout the site to courts, lighting, buildings, irrigation and other facilities.
- Provision of telecommunications to and around the site.

4.9. ADDITIONAL LIGHTING REQUIREMENTS

- All equipment and components utilised in the delivery of the lighting must:
 - a) Be supplied:
 - i. Directly by an Australian manufacturer; or
 - ii. By an authorised Australian supplier or authorised Australian distributor of the manufacturer; and
 - b) Be covered:
 - i. By a manufacturer's warranty; and
 - ii. Where manufactured outside of Australia, under which the authorised supplier or authorised distributor assumes principal responsibility for satisfying the warranty terms and which must be independent from the manufacturer's warranty and must remain valid and enforceable despite any cessation of business by the manufacturer.
- Each warranty required:
 - i. Must be for a reasonable period and on reasonable terms, both being acceptable to RRC
 - ii. Must, unless otherwise approved by RRC, be given by the manufacturer and the relevant authorised supplier or authorised distributor to.

5. FUNCTIONAL CHARACTERISTICS

The required performance specifications for the goods and/or services, focusing on the expected inputs and outputs, rather than the methods used to achieve the performance.

5.1. PERFORMANCE CHARACTERISTICS

The goods and/or services are required to support the delivery of high-quality, durable, and compliant facilities forming part of Stage 1 of the Rockhampton Sports Precinct Netball development. Performance requirements focus on what the outcome must achieve, rather than prescribing the method, materials, or processes used to achieve it.

The goods and/or services must:

- Deliver safe, functional, and competition-ready netball infrastructure that meets relevant national and local sporting standards.
- Enable reliable performance under expected usage levels, including community sport, training, and competitive fixtures.
- Demonstrate durability suitable for outdoor sporting environments, including resistance to weather, UV exposure, and high-traffic use.
- Provide a user-centred experience, ensuring accessibility, safety, and ease of maintenance.

- Achieve performance outcomes that support the long-term operation of the precinct, including efficiency, sustainability, and lifecycle value.
- Integrate effectively with adjacent precinct works and existing site conditions without adverse impact on current or future stages.

The contractor is responsible for selecting appropriate methods, unspecified materials, and construction approaches that meet or exceed these performance outcomes.

5.2. TECHNICAL CHARACTERISTICS

Where performance requirements alone do not sufficiently define the scope, technical characteristics specify the minimum physical, structural, and operational attributes required of the goods and/or services.

Technical requirements include, but are not limited to:

- Compliance with all applicable Australian Standards, building codes, and sport-specific technical specifications for netball facilities.
- Detailed physical characteristics of built elements such as pavement layers, surfacing systems, drainage infrastructure, structural components, lighting systems, and associated amenities.
- Minimum technical tolerances, dimensions, finishes, performance thresholds, and engineering requirements necessary to ensure the quality and safety of the works.
- Requirements relating to materials, coatings, fixings, electrical hardware, mechanical components, and durability benchmarks.
- Specific design or construction features essential to the project (e.g., court orientation, line-marking specifications, slip resistance, stormwater performance, lighting uniformity levels, fencing heights, or service provisions).
- Any mandatory technical deliverables required to ensure full integration with the wider Sports Precinct master plan and future staging.

These technical characteristics must be satisfied regardless of the contractor's chosen construction methodology and are essential to achieving the intended outcomes of Stage 1 of the Rockhampton Sports Precinct Netball development.

6. SEPARATION OF STAGE 1A AND STAGE 1B

For tendering purposes, the Project has been divided into Stage 1A and Stage 1B in accordance with the relevant plan drawings (Sub-stages Sketch Plan - **se_12306_skt_cmp**).

Refer to Tender Schedule 3 – Schedule of Prices and Rates, specifically Stage 1A Item 2.1 (Mains Connections), for pricing. In the event that components of Stage 1B do not progress to award, pricing should allow for the installation of mains connections through Stage 1B in accordance with the drawings and specifications.

Connections associated with Stage 1B are to be excluded from Stage 1A pricing, as they will be captured separately within the Stage 1B pricing schedule for clarity.

7. SOUTHERN SECTION SITE WORKS

The Southern Section of the site requires electrical works due to revised site boundaries and the separation of the childcare facility. Refer to drawing '**Southern Section Site Plan**' (**25015-E-Site-202**) for details. Overhead electrical works shall be undertaken by Ergon, with coordination and facilitation provided by the Contractor. All underground electrical works shall be carried out by the Contractor in accordance with the referenced drawing. These works are to be included within Item 6.0 of the Pricing Schedule.

8. GENERAL

8.1. USE OF 'OR EQUAL OR EQUIVALENT' PRODUCTS

All product and brand names referenced in the Tender Documentation shall be interpreted as “or equal or equivalent.” Any such references are provided solely to indicate the required standard, quality, performance level, or functional characteristics expected for the Works. They do not mandate the use of a specific manufacturer or proprietary product.

Contractors may propose alternative products or materials, provided that the proposed alternatives:

- meet or exceed the performance, durability, safety, and technical requirements of the specified product;
- comply fully with all relevant Australian Standards, codes, and project-specific criteria;
- do not compromise the design intent, interface requirements, or long-term maintainability of the Works; and
- are supported by sufficient technical documentation, certifications, and evidence of suitability.

Acceptance of any proposed equal or equivalent product is at the sole discretion of the Principal or the Principal's Representative. No substitution shall be used until formal written approval has been granted.

8.2. LANDSCAPE MAINTENANCE & ESTABLISHMENT PERIOD

Provide landscape maintenance for a period of 3 months, refer Landscape specification.

8.3. COUNCIL SUPPLIED PLANT STOCK

Council will supply all plant stock including trees. The Contractor shall take delivery of all supplied plant & tree stock ex Council's Kershaw Gardens Nursery at 2 MacAree Street, Berserker, and shall be responsible for the safe loading, handling, transport, and planting of all stock in accordance with the project drawings, specifications, and accepted horticultural practices.

Upon collection from the Nursery, the Contractor shall inspect all plants and immediately notify the Principal of any visible defects, non-conformances, or damage; failure to do so will be deemed acceptance of the stock in good order and condition. From the point of collection, full responsibility for the care, protection, handling, and any loss or damage to the plant stock transfers to the Contractor.

This responsibility remains with the Contractor until Practical Completion of the landscape works, including maintenance of plant health, moisture, and protection from stress, contamination, or physical damage.

9. STANDARDS AND CODES OF PRACTICE

All works carried out under this Contract shall comply with all relevant Australian Standards, industry Codes of Practice, legislative requirements, and regulatory obligations applicable to the nature of the Works. Where a Standard or Code is referenced within the Contract Documents, the latest published edition at the time of tender shall apply unless otherwise specified.

The Contractor is responsible for ensuring that all workmanship, materials, methods, testing, and documentation fully conform to these requirements. In the event of any inconsistency between a Standard, Code, and the Contract Documents, the higher or more stringent requirement shall apply.

The Contractor shall ensure that all personnel, subcontractors, and suppliers engaged in the Works follow recognised industry best practice and perform all activities in accordance with the applicable Standards and Codes at all times.

10. QUEENSLAND PROCUREMENT POLICY 2026

All tenderers must ensure that their proposed works, delivery methods, supply chains, and subcontractor arrangements align with the requirements and strategic pillars of the Queensland Procurement Policy 2026. This includes demonstrating whole-of-life value for Queensland, supporting local and regional supplier participation, complying with all ethical and responsible supplier expectations, incorporating environmentally and socially responsible practices, and identifying opportunities for innovation and improved community outcomes.

Tenderers may be required to provide reporting or evidence to support compliance with these requirements throughout the contract.

11. INNOVATION AND SUSTAINABILITY

The Contractor shall actively pursue and implement innovative construction methods, materials, and technologies that improve project outcomes in efficiency, quality, and whole-of-life performance. Sustainable practices are to be integrated into all stages of the Works, with a focus on minimising environmental impacts, reducing waste, conserving resources, and supporting long-term operational resilience.

Proposals that demonstrate measurable benefits—such as reduced carbon footprint, improved material efficiency, enhanced durability, or lowered maintenance requirements—are encouraged and may be submitted to the Superintendent for consideration and approval.

12. TRAINING AND DEVELOPMENT OPPORTUNITIES

Rockhampton Regional Council is committed to supporting workforce development, skills growth, and long-term industry capability through the procurement and delivery of the Rockhampton Sports Precinct.

In line with Council objectives and relevant State Government requirements, all contractors and suppliers engaged on the project will be expected to demonstrate a strong commitment to training, skills development, and workforce participation outcomes appropriate to the scope and value of the works.

As part of the procurement process, tenderers will be required to outline how they will deliver meaningful and measurable training and development opportunities, including but not limited to:

- Employment and structured training opportunities for apprentices, trainees, and cadets, particularly in construction and related trades and professional disciplines.
- On-the-job skills development, mentoring, and supervision arrangements that support successful completion of training and qualifications.
- Workforce upskilling initiatives that enhance safety, productivity, and technical capability across the project lifecycle.
- Engagement of local training providers and Registered Training Organisations (RTOs) where practicable.
- Clear reporting mechanisms to demonstrate delivery of training commitments and to record verified training outcomes achieved throughout the contract period.

Council places a strong emphasis on active participation in training and the development of a skilled local workforce. Contractors will be expected to embed training initiatives into project delivery and to demonstrate ongoing achievement of these outcomes.

Through these measures, the Rockhampton Sports Precinct procurement will contribute to sustainable employment pathways, increased local skills capacity, and improved long-term outcomes for the Rockhampton region and the Queensland construction industry.

13. WORK HEALTH & SAFETY REQUIREMENTS AND SITE WORK CONDITIONS

The Contractor shall carry out all works in full compliance with the Work Health and Safety Act 2011 (Qld), the Work Health and Safety Regulation 2011, all applicable Codes of Practice, and any other relevant statutory or regulatory obligations. The Contractor is responsible for preparing, implementing, and maintaining a Site-Specific Safety Management Plan that identifies hazards, assesses risks, and outlines the control measures required to ensure the health and safety of all workers, subcontractors, visitors, and members of the public.

The Contractor shall ensure that all personnel are competent, appropriately trained, and inducted prior to commencing work on site, and must maintain a safe working environment at all times through effective supervision, safe work procedures, appropriate PPE, incident reporting, and continuous risk management practices. The Contractor is responsible for securing the site, managing public access, maintaining traffic and pedestrian controls where required, and preventing harm arising from construction activities, equipment, noise, dust, or other site-related hazards.

All work must be conducted in accordance with the site conditions, including environmental constraints, weather considerations, underground and overhead services, existing infrastructure, and any specific conditions identified in the Contract Documents. The Principal reserves the right to audit, inspect, or direct the Contractor to rectify any safety-related non-conformance without delay. Failure to comply with these requirements may result in suspension of works or other actions permitted under the Contract.

14. COMPLIANCE WITH DEVELOPMENT APPROVAL CONDITIONS

Council has Development Approval for the project, and a copy of the approved Development Application (DA) is provided in the Appendix. The Principal Contractor must ensure full compliance with all conditions outlined in the DA.

In particular, the Principal Contractor is required to prepare, submit, and implement the following documents in accordance with Conditions 5, 6 and 7 of the Development Approval:

1. Construction Management Plan (Condition 5)
The Principal Contractor must develop and maintain a comprehensive Construction Management Plan addressing site operations, safety, staging, environmental controls, and community impact mitigation.
2. Erosion and Sediment Management Plan (Condition 6)
The Principal Contractor must prepare and implement an Erosion and Sediment Management Plan that meets all applicable legislative and council requirements, ensuring effective protection of waterways, drainage systems, and adjoining properties during construction.
3. Traffic Management Plan (Condition 7)
The Principal Contractor must prepare and enforce a Traffic Management Plan detailing safe access arrangements, temporary traffic controls, pedestrian movements, and measures to minimise disruption to the surrounding road network.

The Principal Contractor is responsible for ensuring these plans are approved by the relevant authorities (where required), kept current, and adhered to throughout the duration of the works.

15. BUILDING APPROVAL REQUIREMENTS

Council has paid the required QLeave levy and obtained Building Approval for the project. The Principal Contractor must nominate an appropriately licensed QBCC contractor to undertake the construction of the new Clubhouse and Public Amenities Building.

The Principal Contractor is responsible for arranging all required inspections in accordance with the Building Approval, applicable legislation, and certification requirements. Any re-inspections required due to incomplete, defective, or non-compliant work will be at the Contractor's cost.

16. OTHER APPROVALS

Plumbing Approval:

The Plumbing Subcontractor shall be responsible for preparing, coordinating, and lodging all required plumbing approval applications with the relevant statutory authorities, and for the payment of all associated application, inspection, and approval fees.

The Plumbing Subcontractor shall ensure that all documentation is complete, accurate, and submitted in a timely manner to avoid delays to the Works. This shall include the provision of design documentation, certifications, and any supporting information required by the Rockhampton Regional Council as the assessing body. The Subcontractor shall also coordinate and attend all inspections as required to achieve approval.

All plumbing works shall be carried out in accordance with the approved documentation, relevant codes, standards, and authority requirements. Copies of all approvals, certifications, and inspection records shall be provided to the Superintendent upon request.

The actual cost of such fees shall be reimbursed through the Provisional Sums allocated within the Contract.

Sewer and Water Connections:

The Principal Contractor shall be responsible for preparing, coordinating, and lodging all Private Works Applications with Fitzroy River Water (FRW), and for arranging and completing all works associated with the provision of water supply and sewerage service connections to the Site.

This shall include, but not be limited to, coordination with FRW, undertaking all necessary civil and connection works, and ensuring compliance with all applicable standards, specifications, and approval requirements. The Principal Contractor shall also be responsible for coordinating inspections, testing, and commissioning of the services to achieve final acceptance.

All documentation shall be complete, accurate, and submitted in a timely manner to avoid delays to the Works, and copies of all approvals, certifications, and as-constructed records shall be provided to the Superintendent upon request.

The actual cost of associated application and connection fees shall be reimbursed through the Provisional Sums allocated within the Contract.

Ergon Electrical Works:

The Principal Contractor shall be responsible for undertaking all civil works required for the installation of Ergon Energy supplied and installed pad-mounted transformers, including but not limited to excavation, construction of transformer foundations (supply & install precast culverts), conduits, trenching, backfilling, and reinstatement.

The Principal Contractor shall coordinate and liaise with Ergon Energy to ensure the timely provision and installation of electrical infrastructure, including arranging inspections, meeting all technical and access requirements, and facilitating the connection of power to the Site. All works shall be carried out in accordance with Ergon Energy standards, specifications, and approval requirements.

NBN / Telstra Telecommunications:

The Principal Contractor shall liaise with NBN Co and/or Telstra to arrange the provision of telecommunications services to the Site. This shall include, but not be limited to, coordinating the installation of a new telecommunications pit, conduits, and lead-in cabling to the switchroom within the new Amenities Building and extension to the New Netball Club House.

The Principal Contractor shall be responsible for ensuring all civil and enabling works required for the installation within the site are completed in accordance with NBN Co and Telstra standards and specifications, including trenching, conduit installation, backfilling, and reinstatement. The Contractor shall also coordinate inspections, approvals, and connection works to ensure the timely provision of telecommunications services to the Site.

17. SITE REQUIREMENTS

17.1. SITE ACCESS

The Principal Contractor must manage all site access arrangements to ensure safe and efficient movement around the Stage 1 construction area within the Rockhampton Sports Precinct. Access for all construction vehicles, deliveries, subcontractors, and personnel is strictly via Norman Road only.

No construction traffic is permitted to enter, traverse, or utilise access through the adjoining Central Queensland University (CQU) site under any circumstances. The Contractor must ensure all subcontractors, suppliers, and delivery drivers are informed of, and adhere to, this requirement at all times.

The Principal Contractor shall develop, submit, and implement a comprehensive Traffic Management Plan (TMP) for Council approval prior to commencement of works. The TMP must outline proposed access routes, delivery scheduling, traffic interface controls, pedestrian management measures, and protocols for minimising disruption to surrounding road networks and precinct users. The plan must be maintained and updated as required throughout the construction period.

The Principal Contractor is required to coordinate access points, TMP requirements, and all traffic-related measures with Council to ensure safe operations and minimal impact on adjacent land uses and the broader community. Site access arrangements shall be carefully planned, designed, and implemented to minimise disturbance to the natural environment, including the loss or degradation of existing trees and remnant vegetation.

17.2. SITE RESTRICTIONS

Work Area Limits:

The Contractor shall only occupy the designated Stage 1 Netball works areas as identified in the contract drawings and documents unless an alternative arrangement is negotiated and approved by the Principal.

PCBU Responsibilities:

As the Person Conducting a Business or Undertaking (PCBU), the Contractor is fully responsible for ensuring site safety and security. The Contractor must coordinate site access with other contractors, precinct staff, and facility users to ensure safe shared-space operations.

Animals Prohibited:

Dogs are strictly prohibited from entering the construction area, consistent with safety and Council expectations for the precinct.

Confidentiality and Public Interaction:

Contractors, subcontractors, and employees are not permitted to provide information to the public regarding the project. All enquiries must be directed to the Superintendent.

Work Hours:

Contractors must comply with Rockhampton Regional Council–designated work hours as per local by-laws relating to noise and environmental nuisance.

17.3. SITE SERVICES

As no site power or water is currently available for Stage 1 Netball works, the Contractor is responsible for providing all required temporary site services and facilities. These shall include, but are not limited to:

- Portable toilets
- Portable hand-washing stations
- Temporary lighting
- Generators to supply temporary power
- Temporary potable water storage and distribution systems

All temporary amenities and services must be established, operated, and maintained in full compliance with applicable WHS and Council requirements.

17.4. PROJECT IDENTIFICATION SIGNAGE

The Contractor shall install two Council supplied project signs, and maintain all project identification, safety, and regulatory signage in accordance with statutory requirements and Council standards for the Rockhampton Sports Precinct.

17.5. SITE MANAGEMENT

The Contractor must maintain a clean, orderly, and environmentally compliant construction site at all times. All waste, surplus materials, and debris must be routinely collected, removed, and lawfully disposed of in accordance with applicable environmental legislation and Council requirements.

To prevent dirt, sediment, and construction residue being transported onto sealed public roads, the Contractor must install and maintain rumble grids at all approved site exit points. These rumble grids must effectively remove soil and debris from vehicle tyres and undercarriages prior to vehicles entering the public road network. All construction vehicles must utilise these exit points without exception.

In addition to maintaining site cleanliness, the Contractor must implement robust erosion and sediment control measures to prevent soil loss, protect adjoining properties, and safeguard the environment.

17.6. CULTURAL HERITAGE REQUIREMENTS

Council will engage with the Darumbal People to establish an agreement governing the management and handling of cultural heritage matters relating to the proposed sports precinct site.

To satisfy cultural heritage duty of care obligations, an initial Cultural Heritage Assessment will be undertaken. As part of this process, the following will be defined and agreed:

- The study area for assessment
- The nature and scale of proposed work activities
- A preferred cultural heritage management strategy

These measures will ensure that all project activities are conducted in a manner that appropriately identifies, protects, and manages cultural heritage values in accordance with relevant legislative requirements and in consultation with the Traditional Owners.

17.7. TREE PROTECTION REQUIREMENTS

All works in the vicinity of existing trees nominated for retention shall be carried out in accordance with AS 4970:2025 Protection of Trees on Development Sites and the Landscape Specification.

The Contractor shall implement appropriate tree protection measures, including the establishment and maintenance of Tree Protection Zones (TPZs), fencing, and controls to prevent damage to tree roots, trunks, and canopies. No excavation, storage of materials, vehicular access, or ground disturbance shall occur within nominated protection zones without prior approval of the Superintendent.

Any damage to trees resulting from the Contractor's activities shall be made good at the Contractor's expense and may include remediation works or replacement as directed by the Superintendent.

17.8. FAUNA SPOTTER REQUIREMENTS

Prior to and during any tree removal, vegetation clearing, or disturbance of potential habitat areas, the Contractor must engage a qualified and licensed fauna spotter-catcher to be present on site. The fauna spotter shall:

- Inspect all vegetation, hollows, logs, and habitat features prior to clearing.
- Identify, record, and safely manage native wildlife encountered within the work area.
- Supervise clearing activities to ensure fauna is not harmed, injured, or displaced without appropriate handling.
- Undertake relocation of fauna in accordance with legislative requirements and approved animal-handling protocols.
- Provide guidance to site personnel on fauna protection measures and stop-work procedures where required.
- Maintain records of fauna interactions, relocations, and environmental observations for inclusion in project reporting.

No tree removal or mechanical clearing works may commence until the fauna spotter is in position and has confirmed the area is safe to proceed. Clearing activities must be staged to allow fauna to safely vacate the area and to minimise habitat disturbance.

17.9. ENVIRONMENTAL MANAGEMENT REGISTER (EMR)

The site is currently registered on the EMR, early investigations have indicated that there is no contamination on site and it is currently in the progress of being de-listed. However, in the interim all spoil from site is to remain on site or disposed of according to EMR requirements.

17.10. OTHER WORKS IN THE VICINITY

Council will concurrently be delivering the new signalised intersection at Foulkes Street, which will form the main access point to the Rockhampton Sports Precinct. The Contractor must coordinate closely with Council to ensure seamless integration between the intersection works and the new Stage 1 access road and services and including programming, designed interface, and construction sequencing.

17.11. STRIPPED TOPSOIL

Stripped topsoil shall be retained on site and stockpiled for reuse wherever it is assessed as suitable for reinstatement, site rehabilitation or landscaping works. Any surplus topsoil that is not immediately required shall remain onsite and be placed in a designated stockpile area for future use as directed by the Principal.

All topsoil stockpiles must be protected with appropriate erosion and sediment control measures to prevent loss, contamination, or environmental harm.

17.12. COUNCIL-SUPPLIED FILL MATERIAL

Council has identified a suitable source of engineered fill located in close proximity to the Rockhampton Sports Precinct project, at the Council's Gomersall Road site. Approximately 10,000 m³ of residual bulk soil material is available for use by the Contractor.

This fill source, together with its associated geotechnical investigation reports and test results, will be made available for inspection prior to construction. Contractors are responsible for reviewing the material characteristics, suitability, and handling requirements as detailed in the geotechnical documentation. Access for viewing and sampling will be arranged by Council upon request.

The Contractor shall maintain accurate haulage and delivery records for all imported fill transported from the nominated source and provide these records to the Superintendent upon request for the purposes of verifying quantities incorporated into the Works.

18. SCHEDULE OF RATE PROVISIONS

The following Schedule of Rate provisions define the basis for measurement and payment of specific work activities that are dependent on site conditions or require adjustment during construction. These provisions apply only where the relevant conditions are encountered, verified, and directed by the Superintendent in writing. Tendered rates shall be deemed to include all labour, plant, materials, testing, compliance, overheads and profit margins and associated activities necessary to complete the works described. No additional payment will be made beyond the applicable scheduled rates, and strict compliance with notification, verification, and measurement requirements is a condition of entitlement to payment.

18.1. UNSUITABLE SOIL

Unsuitable Soil is material that, when identified and confirmed by the Superintendent, is not fit for its intended purpose and must be removed, treated, or replaced. The Contractor shall notify the Superintendent upon encountering such material and undertake only the works directed in writing.

Payment will be made at the scheduled rates for excavation, disposal, replacement, or stabilisation, measured to the Superintendent's satisfaction, with all testing, haulage, fees, environmental compliance and QA records included in the rates. No payment will be made for material that can be reworked to meet specification or for works undertaken without written direction.

18.2. ROCK

Rock is any natural or man-made material that, in the Superintendent's opinion, cannot be reasonably excavated using standard earthmoving equipment typical of normal earthworks operations (e.g., a 20–30 tonne excavator with standard bucket and ripper).

It includes igneous, sedimentary and metamorphic rock; boulders; cemented or conglomerate materials; and any artificial or man-placed obstructions such as mass concrete, rubble masonry or reinforced concrete that are not shown on the Drawings and could not reasonably have been anticipated from the site information.

Rock excavation shall be measured in cubic metres (m³) in-situ, based on pre- and post-excavation survey surfaces. Measurement will only apply to volumes excavated within the directed boundaries confirmed as Rock by the Superintendent, and only where the Contractor has notified the Superintendent at first encounter and received written direction to proceed.

No allowance will be made for over-excavation, side-slip, batter rounding, or excavation outside the authorised limits. Rates include ripping, mechanical breaking, excavation, handling, loading, haulage, disposal, trimming, environmental controls, QA records, and associated plant and labour.

18.3. PILES

The Contractor shall provide a fixed rate per linear metre for any piling installation that exceeds the documented design embedment depth. Where the Superintendent directs that piles be driven or installed beyond the specified embedment, the Contractor shall carry out the additional works at the tendered per-metre over-depth rate. This rate shall be deemed to include all labour, plant, materials, testing, and associated activities necessary to achieve the additional depth, with no further cost payable by the Principal.

18.4. IMPORTED FILL (Client Supplied)

The Contractor shall provide a fixed unit rate per cubic metre (m³) for the supply of client-supplied fill only, including the loading of material from the nominated source and delivery to the Works.

The rate shall be deemed to include all costs associated with accessing the source, excavation, handling, stockpiling (if required), and haulage to site, but shall exclude placement, compaction, trimming, and any in-situ processing within the Works.

18.5. IMPORTED FILL (Contractor Sourced)

The Contractor shall provide a fixed unit rate per cubic metre (m³) for their own Contractor- sourced fill, including the winning and loading of material from their own nominated source and delivery to the Works.

The unit rate shall be deemed to include all costs associated with source identification and access, excavation, handling, stockpiling (if required), and haulage to site, but shall exclude placement, compaction, trimming, and any in-situ processing within the Works.

19. AS CONSTRUCTED DOCUMENTATION AND ASSET IDENTIFICATION

All as-constructed drawings and data must be provided at completion of the works, and it is the Contractor's responsibility to update all design drawings to accurately reflect the infrastructure as installed and executed, with the Principal supplying the original/source CAD drawings required for this purpose.

Contractor is responsible for the provision of all required documentation, including approvals, test certificates, survey data, and RPEQ certification, as part of the as-constructed submission

Submission of as-constructed data in ADAC-compliant XML format is a mandatory requirement of Rockhampton Regional Council for all developments involving infrastructure that becomes Council assets.

20. CRITICAL DATES

The Contractor is to be aware that in order to meet delivery time frames for the development, the following method of award will apply.

Letter of Acceptance – Contract Starts	
Prestart Meeting	2 weeks after letter of acceptance.
Offsite works (construction manuals, Ordering Materials, letting of Trades etc.)	At letter of acceptance
Possession of Sites	14 days from letter of acceptance subject to clause 6.2B of the Conditions of Contract
Onsite works period	Program to be supplied by Contractor.

The Contractor is required to submit a detailed construction program and methodology statement covering the scope as detailed in item 4.

Construction program shall detail the following:

- a Description and timing of all activities.
- b Ordering of long lead time items.
- c Milestones.
- d Witness points for inspection of key areas of the Inspection Test Plan (ITP);

- e Workshop drawings and submissions if required.
- f Risks identified and control measures to mitigate affects to the schedule.
- g Planned service interruptions.
- h An allowance for 5 days for inclement weather or a latent condition.
- i Allowance for holidays and industry RDO's; and
- j The estimated value of work completed for each month.

21. FORM OF PROGRAM

The Construction Program shall:

- a be prepared using MS Project software or similar approved by the Superintendent in the form of a time scaled critical path network and shall meet the following criteria:
- b the network shall accurately represent the Contractor's Construction Program for carrying out the work under the Contract;
- c Only one (1) critical path shall be identified at all times;
- d The work under the Contract shall be defined in separate activities as performed by each trade of subcontractor on each element or group of elements;
- e The duration of each activity shall have one time estimate expressed in working days. This activity duration should, as a general rule, not exceed 10 working days. Where this extends beyond a period of 10 working days (for example the procurement of materials, plant and equipment) such activities where practicable must be broken down into sub-activities;
- f the Contractor shall ensure that the total resources required for the execution of the work in accordance with the Construction Program will be at all times within the level of resources which it can provide. The Construction Program shall clearly show the installation and removal of all temporary plant and equipment necessary for the construction of the works and shall identify any constraints in the adjoining work;
- g each activity shall be represented by a description referring to a specific part of the works, which will permit its easy and accurate identification;
- h each activity shall be identified by a unique number;
- i Lead times for supply of information, selection of subcontractors and suppliers, approvals, or supply of equipment by the Superintendent or its agents shall be represented separately from the Site activity for relevant items. Lead times shall comply with any relevant provisions of the Contract and may be presented either in the Construction Program or in separable schedule form;
- j Significant off-Site activities such as the supply and delivery of material required by the Contractor, or by a subcontractor shall be expressed as separate network activities;
- k the Construction Program shall show in respect of all services, the detailed activities representing the coordinated completion, performance and other testing and certification required by Legislative Requirements and as necessary under the Contract;
- l The Construction Program shall clearly indicate all milestone dates such as dates for access and the Date for Practical Completion. The use of imposed constraint dates within the Construction Program

shall be limited to those milestones. All other activities and milestones shall be scheduled using the appropriate logical dependencies;

- m The Construction Program shall be prepared using resource levelling techniques. Resource logic dependencies may be shown where required to indicate logical dependencies from limited crew sizes and/or number of crews;
- n Where details of work under the Contract to be performed are not available, the Contractor shall program the work to the best of his ability. The logic for the construction of this work will then be amended as necessary when sufficient details become available. The required logic changes will then be incorporated in the monthly construction program update, after agreement by the Superintendent; and
- o Update programme as required, a revised construction program shall be submitted with each payment and extension of time claim.

22. QUALITY ASSURANCE

For all the works under the contract, including work by subcontractors, the Contractor shall plan, establish, implement and maintain a Quality Plan. The Quality Plan is to include a description of the project management structure for the delivery of the project including responsibilities and authorities.

22.1. STANDARDS FOR DESIGN, MATERIALS & WORKMANSHIP

Unless approved or specified otherwise, the standards applicable to the contract works shall be current Capricorn Municipal Development Guidelines, Australian, Australian/New Zealand and/or ISO standards.

When referencing standards, it does not remove the obligation to finish the Works in a Tradesman like manner and final acceptance is at the sole discretion of the Principal and/or Superintendent.

All materials used on the project shall be new, of the latest batch and deemed by the Superintendent as fit for the purpose. All plant, materials and workmanship shall be to industry best practice and highest quality.

22.2. INSPECTION, TESTING & CERTIFICATION OF THE WORK

Periodic inspection by Council and other stakeholders will also be arranged by Council.

The Contractor is to allow for all other inspections, tests and certification of the works as required.

22.3. INSPECTION AND TEST PLAN

The Contractor is to prepare and maintain a detailed Inspection and Test Plan (ITP), checklists, submissions and certification for the works.

23. MEDIA RELEASES

The Contractor, Contractor's employees, subcontractors or suppliers shall not issue any information, publication, document, or article for publication concerning the project in any media including social media without prior approval of the Principal. The Contractor shall refer any enquiries concerning the project from any media to the Principal.

24. PROJECT COMPLETION / PRACTICAL COMPLETION

24.1. FINAL CLEANING

Before the date for Practical Completion, clean exterior surfaces and debris from the site drainage systems. Remove all waste and surplus materials. Remove non-incorporated works such as temporary access and sediment control.

24.2. PRE-PRACTICAL COMPLETION REQUIREMENTS

Prior to Certification of Practical Completion, the Contractor must have completed the following;

- Submit all required documentation, including as-constructed drawings, and quality records, certifications and approvals .
- Prepare defects list, rectify defects, submit original list to Superintendent when notifying request for Practical Completion.

25. QUANTITIES

This is a lump sum contract. It is the Contractor's responsibility to calculate all quantities and include all materials, labour, plant and equipment necessary to carry out the works. Where quantities are given, they are an estimate only and do not form part of the contract.

26. SUBCONTRACT

The Principal Contractor shall furnish the Superintendent with a list of proposed subcontractors and suppliers when requested. The Contractor is not to depart from the approved list without written consent from the Superintendent.

27. APPENDIX FOLDERS

All Works under this Contract shall be performed in accordance with the current version of the following documents outlined within the drawing and document transmittal included in the Appendix Folders to this Tender Document. The documents contained within the Appendix Folders must be read in conjunction with Part 2 Technical Specification.

The Appendix Folder is available for download from:

<https://rockhamptonregion.sharefile.com/public/share/web-s6a4822b5c84047689c3238b659a8bdb1>