

Rockhampton Sports Precinct – Netball

Addendum 01

For all interested parties intending to tender for the ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL, please find included with this addendum the following clarifications to assist with your tender submission:

1. Can Council please provide the CAD files?

Please refer to attached .zip file “SE_12306_TC001_RSP Stage 1 Layouts_02-07-2026 (For Information Only).zip” which contains the following CAD layouts produced as part of Stage 1 100%DD / Issue for Tender:

- Civil site layout: x01_pf_02-07-2026 (For Information Only).dwg
- Civil drainage layout: x01_pd_02-07-2026 (For Information Only).dwg
- Landscape site layout: 24523-ST1-MDC-L-SITE_02-07-2026 (For Information Only).dwg

Please note we are transmitting the CAD data on the basis set out in this document. Sporteng have produced the CAD data using AutoCAD 2020 and 12d Model v14. The CAD data is supplied only as a means to assist in the production of work. There may be discrepancies within the CAD data and the data should always be checked against the PDF issue of drawings which is for all purposes the reference copy and/or the controlled electronic copy. All relevant dimensions are shown on the PDF issue and the CAD data should not be used to derive any dimensions. The user is responsible for anything they produce using all or part of the CAD data. While we take reasonable measures to carry out checks, we do not accept responsibility for any loss arising from computer viruses.

2. Civil: Please confirm heights on bulk earthwork drawings take the cut/fill to a height that is shown on the detail as either “Design CBR 1.5% or Subgrade”

Confirming that the cut / fill depths shown on the bulk earthworks drawing (SE_12306_F1150, F1151) represent works required to achieve the design subgrade levels. Where stabilisation is shown within pavement profiles, the design subgrade level is the top of the stabilised layer; material to be stabilised is either general fill or in-situ material. As per notes on SE_12306_F1150, the netball courts include over-excavation (shown in yellow dashed lines) to provide consistent fill platforms beneath each court, with the consistent fill platform volumes included in the cut / fill balance.

3. Can Council produce the vegetation and fauna management plan

Please find attached Vegetation and Fauna Management Plan.

4. Are there any photos, soil reports and geo information for the 10,000m3 stockpile at Gomersall Road site?

We have engaged a Geotech consultant to undertake further testing of this stockpile. We will provide once this is finalised.

5. With reference to the SportEng document titled ‘SE_12306_SKT_CMP_SUB-STAGES AND CONSTRUCTION MANAGEMENT PLAN_B’ the plan indicates locations for the top-soil stockpile and site compound locations. However, according to the site clearing and bulk earthworks plans, these areas have not been captured. Please clarify.

Site clearing and bulk earthworks plans relate to the construction footprint and as the site office and stockpile areas exist outside the construction zone, they do not require the same level of detail. Contractor is to clear for the site office, entry roadway and stockpiles as required.