

Rockhampton Sports Precinct – Netball

Addendum 02

For all interested parties intending to tender for the ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL, please find included with this addendum the following clarifications to assist with your tender submission:

Please find information below from the site inspection held at 10:00am, Monday 6 July 2026.

- Secondary access to site via the Foulkes Street Intersection? Secondary access could not be achieved as Council would be constructing the Intersection. One could be installed in the location we were previously at.
- Size of trees to be removed that require replacement? 350mm diameter, chest height. Trees to be retained are marked on plans.
- Is Council supplying all tree stock? Yes
- Council supplied fill – Can tenderers view? Yes, stockpile is in Gomersall Street.
 - No spoil to leave site. Trees to be mulched on site.
 - Any possibility for additional Council supplied soil? Testing is currently being undertaken on additional soil, for the purposes of tendering, please use the specified amount (10,000m3) in the Tender docs as what will be supplied.
- No entry to site/usage via internal University roads.
- Wildlife on site to be aware of? Kangaroos, no koalas sighted however the northern residential site has been identified as potential koala habitat (not RSP site).
- Scope responsibility for water to the site? Refer to the drawings.
- Power
 - Civil Works are the responsibility of the Contractor – refer to drawings.
 - Power Connection and Transformer are the responsibility of Ergon Energy.
- Sewage Pump Station will be getting installed by Council. Depth of sewer marked on plans.
- Query regarding soil acidity – Discussed on site and advised no issues.
- Query regarding sourcing low pyrite asphalt – discussed on site, tenderer advised to price what they could source.

Please note that receipt of this Addendum must be acknowledged when submitting your tender.