

Rockhampton Sports Precinct

Addendum 5

For all interested parties intending to tender for the ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL, please find included with this addendum the following clarifications to assist with your tender submission:

1. **Please confirm 25mm² XLPE runs required to 2 x Poles from each Netball Court Distribution Board. (DB-FNB.1 – Pole 2 & 3, DB-FNB.2 – Pole 8 & 9 & DB-FNB.3 – Pole 16 & 17) all other circuits are 16mm² including poles that are further away. It is also noted that there are 2 x 25mm² pole light circuits from each Recreational Area DB's. DWG - 25015-E-Site-304 & 25015-E-Site-306?**

This is not correct, due to drafting error. Please allow for 16mm² cable to each poles.

2. **Please confirm that each pole in recreational area requires its own 3 phase 16mm² feed as per SLD DWG 25015-E-Site-306?**

Due to the expected small loads to each poles, it is possible that each poles be provided with single phase 16mm² per pole. However, the voltage drop to each poles will need to be considered.

At the moment we have calculated the voltage drops as per the 3-phase cables that we have proposed in the drawing. If single phase cables are to be proposed, the contractors would need to confirm the voltage drops.

Refer to attached drawings 25015-E-Site-304 and 25015-E-Site-306 (Rev T2).

3. **Drawing LD-2105 - The small connecting path in the upper middle section (connected to the double door fencing) is shown as LHS3, which per the schedule is stamped asphalt. However, the civil drawing (SE_12306_F1600) shows concrete pavement for this area.**

Could council please confirm the correct surface finish for the path so we can ensure our pricing reflects the intended scope?

Updating previous information supplied in Addendum no. 7 – Confirming this is L.HS4-Standard concrete path. Refer to landscape plan LD-2104- [T2]

4. **Drawing LD-2104 - The path at the bottom right corner (connecting the hatched carpark area to the tennis courts) has a symbol indicating LHS3, however the label reads LHS4. Could council please clarify which surface finish applies to this path?**

If it is LHS3, the schedule indicates stamped asphalt, however the civil drawing (SE_12306_F1602) shows concrete pavement, not asphalt.

Updating previous information supplied in Addendum no. 7 – Confirming this is L.HS4-Standard concrete path. Refer to landscape plan LD-2105- [T2].

5. **With reference to the civil drawings (F1604), the path from the netball courts to the district park area 2 is labelled as a Type 3 Asphalt Acrylic Courts.**

However, according to the landscape drawings (LD-2105), this path is labelled as LHS3 which is a stamped asphalt with decorative colour application. Please clarify.

Updating previous information supplied in Addendum no. 7 – As per landscape plan LD-2109 this is L.HS3- Stamped asphalt. Note that similar discrepancies have been captured and clouded in the documents listed.

6. RS04 and RS20 are not detailed in the door schedule shown on sheet AR-NBC-5102 – can you please provide details for these doors

Please find attached revision - MOD-AR-NBC-5102-T2-DOOR & WINDOW SCHEDULES

7. Please confirm if electrical subcontractors are required to have the AS/NZS ISO 9001 accreditation in accordance with Clause 4.1 of the Electrical Services Specification?

Electrical subcontractors will not be required to meet Electrical Services Specification Clause 4.1 – Quality Management System. This clause shall be removed.

Please note that receipt of this Addendum must be acknowledged when submitting your tender.