



13 July 2026

Our Ref: 16699

TENDER NUMBER TEN16699

ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL

ADDENDUM NO. 8

Dear Tenderer,

This addendum forms part of, and is to be read in conjunction with, Invitation to Tender No. TEN16699

For all interested parties intending to tender for the ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL, please find included with this addendum the following clarifications to assist with your tender submission:

- 1. Please confirm that the new Telstra/ NBN lead in and pits shown on E-Site-202 to reticulate along the new road reserve on Darambul Rd are by Telstra/ NBN and not part of this scope – lead in conduits to boundary for existing softball and graduation buildings only as part of this scope?**

All Telstra/Fibre cabling and pits shown on E-Site-202 are not part of the scope for this stage of the project.

- 2. Please specify stormwater attenuation and filtration requirements and calculations so alternatives can be tendered**

Please refer attached SE_12306_RPT006_B Design Report for this information.

- 3. Can council also provide the CAD model for earthworks quantities and/or a level markup**

Please find attached SE_12306_3DM001_STG1_DESIGN_3D Component_13-07-2026.dwg. This represents the Civil finished surface level (FSL) tin which is suitable for tendering purposes but not construction.

- 4. The external finishes schedule for the New Clubhouse details for M.BL – Blockwork to be a honed/polished finish as per a detail on sheet AR-NBC-1260. Can you please re-issue the detail as there is no delineation between honed/polished or plain blockwork. Can you please also advise the specification for the block type.**

Predominantly honed (or standard) finish blockwork with polished feature blocks. Provide a maximum of 10 polished blocks per 2.0 m wall length, arranged generally in accordance with Pattern Types A, B and C shown. The pattern may be adjusted at corners, wall junctions and openings, where honed (or standard) blocks shall

continue and the pattern recommenced beyond the interruption. Refer attached drawings AR-NBC-2001 Rev T2 and AR-NBC-2002 Rev T2

5. **Could Council please confirm the following discrepancies in the stormwater schedule? One would assume the headwalls match the pipe/culvert diameter?**

01-01 HEADWALL OUTLET 375? - Suggested 0.25 - Proposed
10-01 HEADWALL OUTLET 375? - Suggested 0.25 - Proposed
11-01 HEADWALL OUTLET 375? - Suggested 0.25 - Proposed
12-01 HEADWALL OUTLET 375? - Suggested 0.25 - Proposed
19-01 HEADWALL OUTLET 375? - Suggested 0.25 - Proposed
25-01 HEADWALL OUTLET 300? - Suggested 0.25 - Proposed
26-01 HEADWALL OUTLET 700x300 rcbc – To suit 0.25 - Proposed
81-01 HEADWALL OUTLET 225? - Suggested 0.25 - Proposed
87-01 HEADWALL OUTLET 150? - Suggested 0.25 - Proposed

Pit diameter not relevant to headwall outlets (only circular chambers) and can be ignored.

6. **Can Council please advise on the following; I refer to electrical services drawings 25015-E-Site-203, at some of the light poles for the SL1's there is a street lighting cable joint pit. As there is an 80mm conduit feed along these routes to the poles, we are assuming there is a pit at EACH light pole as there is no way you can turn up 2 x 80mm conduits under a light pole. Does not show one at each pole nor can I see any clarification on this. We are also assuming the same will apply at all poles including around the Net ball Courts etc**

Can Council please provide additional details, we are assuming the cables are cut at each pit, fused and then run up to the light poles. Need details of what is actually required please.

This is part of the contractor's design input which is identified in the specification. Pits can be installed wherever the contractor deems necessary as per the spec and applicable standards, with the requirement that all the pits and conduits are accurately captured on the ADAC as cons.

14.1.5.3. Underground Installation

Underground consumer mains shall be installed in accordance with AS/NZS 3000 including but not limited to:

- *Minimum cover of 600 mm below finished surface in traffic areas, 500 mm in non-traffic areas.*
- *Sand surround 75 mm above and below cables, compacted backfill to finished levels.*
- *Cable marker tape ('Electricity Cable Below') at 300 mm above cable and at finished surface.*
- *Concrete encasement where mechanical protection is required or where cables cross other services.*

- Draw pits at direction changes, intervals not exceeding 50 m, and at building entries.
- Conduits of orange HD PVC conduit to AS/NZS 2053, 150% fill maximum, with draw ropes and end seals.

14.1.5.4. Pits and Manholes

Pits shall be precast concrete with heavy-duty access covers (load class per site conditions, minimum Class B for pedestrian areas, Class D for trafficable). Pits shall drain to a soakage pit or stormwater via a gravel sump. Minimum clear internal dimensions:

- Draw pits (straight runs): 600 × 600 × 900 mm deep.
- Junction pits (direction changes, branches): 900 × 900 × 1,200 mm deep.
- Main transition pits (between property boundary and building): 1,200 × 1,200 × 1,500 mm deep.
- All conduits entering pits shall be installed with bell ends.

Please note that receipt of this Addendum must be acknowledged when submitting your tender. For this purpose, acknowledgment of Addendum No. 8 is also attached for completion and return with your Tender Submission.

Yours faithfully



Marie Grund
Contracts & Tenders Supervisor

INVITATION TO TENDER NO.: 16699

ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL

ACKNOWLEDGEMENT OF ADDENDUM

This page is to be inserted in the Tender Submission Document directly in front of the Tender Form if applicable or in front of any other Acknowledgment of Addenda which has previously been issued.

ADDENDUM NO.8

Receipt of the above addendum is acknowledged.

NAME OF TENDERER:

SIGNATURE: _____ FOR AND ON BEHALF OF

TENDERER: _____

DATE: _____