



20 July 2026

Our Ref: 16699

TENDER NUMBER TEN16699

ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL

ADDENDUM NO. 9

Dear Tenderer,

This addendum forms part of, and is to be read in conjunction with, Invitation to Tender No. TEN16699

For all interested parties intending to tender for the ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL, please find included with this addendum the following clarifications to assist with your tender submission:

- 1. Please confirm 25mm² XLPE runs required to 2 x Poles from each Netball Court Distribution Board. (DB-FNB.1 – Pole 2 & 3, DB-FNB.2 – Pole 8 & 9 & DB-FNB.3 – Pole 16 & 17) all other circuits are 16mm² including poles that are further away. It is also noted that there are 2 x 25mm² pole light circuits from each Recreational Area DB's. DWG - 25015-E-Site-304 & 25015-E-Site-306?**

This is not correct, due to drafting error. Please allow for 16mm² cable to each poles.

- 2. Please confirm that each pole in recreational area requires its own 3 phase 16mm² feed as per SLD DWG 25015-E-Site-306?**

Due to the expected small loads to each poles, it is possible that each poles be provided with single phase 16mm² per pole. However, the voltage drop to each poles will need to be considered.

At the moment we have calculated the voltage drops as per the 3-phase cables that we have proposed in the drawing. If single phase cables are to be proposed, the contractors would need to confirm the voltage drops.

Refer to attached drawings 25015-E-Site-304 and 25015-E-Site-306 (Rev T2).

- 3. Drawing LD-2105 - The small connecting path in the upper middle section (connected to the double door fencing) is shown as LHS3, which per the schedule is stamped asphalt. However, the civil drawing (SE_12306_F1600) shows concrete pavement for this area.**

Could council please confirm the correct surface finish for the path so we can ensure our pricing reflects the intended scope?

Updating previous information supplied in Addendum no. 7 – Confirming this is L.HS4-Standard concrete path. Refer to landscape plan LD-2104- [T2]

4. **Drawing LD-2104 - The path at the bottom right corner (connecting the hatched carpark area to the tennis courts) has a symbol indicating LHS3, however the label reads LHS4. Could council please clarify which surface finish applies to this path?**

If it is LHS3, the schedule indicates stamped asphalt, however the civil drawing (SE_12306_F1602) shows concrete pavement, not asphalt.

Updating previous information supplied in Addendum no. 7 – Confirming this is L.HS4-Standard concrete path. Refer to landscape plan LD-2105- [T2].

5. **With reference to the civil drawings (F1604), the path from the netball courts to the district park area 2 is labelled as a Type 3 Asphalt Acrylic Courts.**

However, according to the landscape drawings (LD-2105), this path is labelled as LHS3 which is a stamped asphalt with decorative colour application. Please clarify.

Updating previous information supplied in Addendum no. 7 – As per landscape plan LD-2109 this is L.HS3- Stamped asphalt. Note that similar discrepancies have been captured and clouded in the documents listed.

6. **Could we please request the architectural and structural IFC model for construction sequencing purposes?**

Please refer to .zip file “SE_12306_TC007_RSP Stage 1 Building .ifc_15-07-2026 (For Information Only).zip” via this link – <https://rockhamptonregion.sharefile.com/d-s4849294462924e66b942e4de9eae4f8d>, which contains the following:

1. Netball Building, Structures model: 25015-S-NBC-RT1.ifc
2. Public Amenities Building, Structures model: 25015-S-PAM-RT1.ifc
3. Netball Building, Architecture model: 24523_RHSP_NBC_IFC.ifc
4. Public Amenities Building, Architecture model: 24523_RHSP_PAM_IFC.ifc
5. CAD RELEASE.pdf (applicable files listed within document)

The models contained within this file are suitable for tendering and sequencing purposes but not construction, refer to Item 5 for further details of suitability of model usage as well as the following disclaimer for Item 1 and 2 as per the below:

The information contained within this model is a digital representation of MODE's design intent for this part of the project. It has been provided as information only to assist in the collaboration and coordination throughout the project. The model, and sheets within, are considered dynamic, or uncontrolled, and form only part of the design/documentation process, and so may not represent the latest definition of building elements in either form or dimension.

It is recommended that a thorough review and evaluation of this model be undertaken by the user, prior to its use, to understand its suitability for the expected task. By using this model, it is agreed that it shall be used for its intended purpose only and will not be distributed to others without MODE's approval.

- 7. RS04 and RS20 are not detailed in the door schedule shown on sheet AR-NBC-5102 – can you please provide details for these doors**

Please find attached revision - MOD-AR-NBC-5102-T2-DOOR & WINDOW SCHEDULES

- 8. Please confirm if electrical subcontractors are required to have the AS/NZS ISO 9001 accreditation in accordance with Clause 4.1 of the Electrical Services Specification?**

Electrical subcontractors will not be required to meet Electrical Services Specification Clause 4.1 – Quality Management System. This clause shall be removed.

Please note that receipt of this Addendum must be acknowledged when submitting your tender. For this purpose, acknowledgment of Addendum No. 9 is also attached for completion and return with your Tender Submission.

Yours faithfully



Marie Grund
Contracts & Tenders Supervisor

INVITATION TO TENDER NO.: 16699

ROCKHAMPTON SPORTS PRECINCT – STAGE 1 NETBALL

ACKNOWLEDGEMENT OF ADDENDUM

This page is to be inserted in the Tender Submission Document directly in front of the Tender Form if applicable or in front of any other Acknowledgment of Addenda which has previously been issued.

ADDENDUM NO.9

Receipt of the above addendum is acknowledged.

NAME OF TENDERER:

SIGNATURE: _____ FOR AND ON BEHALF OF

TENDERER: _____

DATE: _____